CUSTOMER	PROPERTY	PROPOSAL DATE
Arrigo CDJR Sawgrass	5901 Madison Ave, Tamarac, FL 33321	September 30, 2026

PRIVATE CLIENT PROPOSAL / MORGAN AUTOMOTIVE GROUP

Arrigo CDJR Sawgrass

Commercial HVAC Replacement Proposal

5901 Madison Avenue | Tamarac, FL 33321
Prepared for Al Garcia



YOUR TWO-SYSTEM REPLACEMENT INVESTMENT

$96,911.13

Unit 9 | 15 ton | Second-Floor Executive Area
Unit 10 | 20 ton | Service Advisor Room

02 SYSTEMS **6% PACKAGE DISCOUNT** **$9,643.61 SAVINGS**

Proposal 2849-AC | Original date: September 30, 2026
Presentation revised: October 9, 2026 | Original 30-day validity retained

Building photo: CarGurus / Arrigo Sawgrass listing

O'BRIEN AC & CONSTRUCTION SERVICES, LLC
4901 NW 17th Way #408 | Fort Lauderdale, FL 33309
(954) 205-1381 | obrienac.com | License CAC1822829

CUSTOMER	PROPERTY	PROPOSAL DATE
Arrigo CDJR Sawgrass	5901 Madison Ave, Tamarac, FL 33321	September 30, 2026

01 / SECOND-FLOOR EXECUTIVE AREA

Unit 9 | 15-ton replacement

Lennox commercial split system | 460V / 3-phase / 60Hz | R-454B
Lennox Quote #784984 / Project #1185264

Equipment / designation	Model / item	Qty
Condensing unit - Unit 9	EL180KCSDT1G / 30Z62	1
Matching standard air handler	EL180KASD-1G / 30Z13	1
Commercial programmable thermostat	CS7500 / 24K41	1
20 kW electric heat, 460V / 3Ph	38C28	1

EQUIPMENT NOTES

Replaces the existing Trane TTA180B400EA condensing unit. Factory refrigerant leak detection. Air handler: 6,000 CFM at 0.8 in. w.c. ESP; 11.0 EER / 14.2 IEER. Thermostat and electric heat are field installed.

INSTALLATION SCOPE

• Recover existing refrigerant and properly dispose/recycle the retired condensing unit and air handler.

• Acid flush the existing refrigerant line set to remove residual oil, moisture and contaminants.

• R-454B charge: 43 lb total at 25-ft line set (21 lb Circuit 1 + 22 lb Circuit 2, including factory holding charge); adjust for actual line length.

• Provide crane rigging and all labor to set and install the replacement condensing unit and air handler.

• Fabricate and install duct transition plenums as required; reconnect electrical, condensate, thermostat and control wiring.

• Complete startup, commissioning and verification of operation, including miscellaneous parts, hardware and consumables for a complete installation.

CUSTOMER	PROPERTY	PROPOSAL DATE
Arrigo CDJR Sawgrass	5901 Madison Ave, Tamarac, FL 33321	September 30, 2026

02 / SERVICE ADVISOR ROOM

Unit 10 | 20-ton replacement

Lennox commercial split system | 460V / 3-phase / 60Hz | R-454B
Lennox Quote #791181 / Project #1194345

Equipment / designation	Model / item	Qty
Condensing unit - Unit 10	EL240KCSDT1G / 30Z65	1
Matching standard air handler	EL240KASD-1G / 30Z16	1
Commercial programmable thermostat	CS7500 / 24K41	1
20 kW electric heat, 460V / 3Ph	38C28	1

CONDENSING UNIT

Two compressors, three cooling stages and factory refrigerant detection. Approximate unit weight: 864 lb.

MATCHING AIR HANDLER

8,000 CFM design airflow; R-454B compatible. Approximate unit weight: 799 lb.

Published performance	Specified value
Nominal cooling	20.0 tons
Net total / sensible cooling	224.7 MBH / 176.7 MBH
Supply airflow	8,000 CFM
Efficiency	11.0 EER / 14.2 IEER
Electric heat / power	20 kW / 460V / 3Ph / 60Hz

Existing dual-circuit refrigerant piping will be reused where serviceable, subject to the specified flushing, testing and evacuation.

CUSTOMER	PROPERTY	PROPOSAL DATE
Arrigo CDJR Sawgrass	5901 Madison Ave, Tamarac, FL 33321	September 30, 2026

03 / SERVICE ADVISOR ROOM

Unit 10 | Installation scope

• Recover existing refrigerant in accordance with EPA Section 608 requirements; properly dispose/recycle retired equipment and recovered refrigerant as applicable.

• Remove and dispose of the outdoor condensing unit and remove the indoor air handler, including required disconnections.

• Remove shelving as required to create safe access for the indoor air-handler replacement.

• Perform two refrigerant line flushes, one per circuit, followed by nitrogen pressure testing and deep-vacuum evacuation.

• R-454B charge: 39 lb 14 oz total at 25-ft line set (19 lb 15 oz per circuit, including factory holding charge); adjust for actual line length.

• Repair the existing duct opening / duct hole and fabricate/install local sheet-metal transitions as required.

• Furnish and coordinate crane service. A $2,000 crane allowance is included in the 20-ton proposal price.

• Rig, set, secure and install the new condensing unit and matching air handler; reconnect electrical, condensate, controls, thermostat and electric heat.

• Complete startup, commissioning, refrigerant charge verification, airflow verification, temperature split verification and confirmation of proper system operation.

CUSTOMER	PROPERTY	PROPOSAL DATE
Arrigo CDJR Sawgrass	5901 Madison Ave, Tamarac, FL 33321	September 30, 2026

04 / INDIVIDUAL AND COMBINED PRICING

Your replacement investment

Each system may be approved individually at its Arrigo / Morgan Tier price. Approve both together under one purchase authorization for an additional 6% package discount.

Unit / served area	Standard price	Arrigo discount	Individual total
Unit 9 / 15 ton Second-Floor Executive	$48,331.74	-$2,234.79	$46,096.95
Unit 10 / 20 ton Service Advisor Room	$58,223.00	-$1,223.00	$57,000.00

Two-system package	Amount
Combined individual discounted prices	$103,096.95
Additional 6% package discount	-$6,185.82
TOTAL PACKAGE PRICE	$96,911.13

TOTAL SAVINGS VERSUS STANDARD PRICES

$9,643.61

COMBINED APPROVAL INCENTIVE

The additional 6% package discount is contingent upon acceptance of both Lennox replacement systems together. If only one system is approved, the applicable individual Arrigo / Morgan Tier price above will apply.

Pricing and discount amounts are carried over from proposal 2849-AC. This presentation updates system identification and visual styling.

CUSTOMER	PROPERTY	PROPOSAL DATE
Arrigo CDJR Sawgrass	5901 Madison Ave, Tamarac, FL 33321	September 30, 2026

05 / CLARIFICATIONS

Scope boundaries & exclusions

• Primary electrical service upgrades, panel replacements, feeder changes, breakers beyond direct equipment reconnection, or transformer changes are excluded unless specifically added by written change order.

• Building Management System (BMS) integration, programming, networking, and modified BMS points are excluded unless specifically listed by written addendum.

• Fire alarm integration, smoke detector work, and fire alarm contractor services are excluded.

• Permit fees and inspection fees are excluded unless specifically added in writing.

• Structural engineering, structural reinforcement, equipment curb/platform replacement, roofing repair, and waterproofing beyond normal mechanical penetrations are excluded.

• Replacement of concealed or inaccessible refrigerant piping is excluded. Existing line sets are assumed reusable after the specified flushing, pressure testing, and evacuation.

• Major duct-system replacement, air-distribution redesign, third-party test and balance, and work beyond the local transitions described above are excluded.

• Temporary cooling is excluded.

• Work is priced for normal business-hour installation unless alternate scheduling is specifically agreed in writing. After-hours or weekend work may require a change order.

• Equipment availability and manufacturer pricing are subject to supplier availability at time of order.

• Any concealed conditions, code deficiencies, damaged existing piping, inaccessible routing, structural conflicts, or site conditions not visible prior to demolition may require additional work by written change order.

CUSTOMER	PROPERTY	PROPOSAL DATE
Arrigo CDJR Sawgrass	5901 Madison Ave, Tamarac, FL 33321	September 30, 2026

06 / WARRANTY AND COMMERCIAL TERMS

Installation notes & terms

Item	Included / applicable
System 1	Unit 9 / Second-Floor Executive Area Lennox 15-ton commercial split system
System 2	Unit 10 / Service Advisor Room Lennox 20-ton commercial split system
Power / refrigerant	460V / 3 Phase / 60Hz / R-454B
Thermostats / heat	Lennox CS7500 / 20 kW, 460V / 3Ph per system
Warranty	One year O'Brien labor warranty; manufacturer equipment warranties per Lennox terms

TERMS & CONDITIONS

• This proposal is valid for 30 days from September 30, 2026 and is subject to equipment availability and manufacturer pricing at time of order.

• O'Brien AC & Construction Services, LLC provides a one (1) year labor warranty from substantial completion. Manufacturer warranties apply in accordance with Lennox warranty terms.

• Any change in scope, field conditions, equipment requirements, code requirements, or customer-requested work outside the scope above may result in a written change order.

• Equipment will be ordered after written acceptance and any required deposit / purchase authorization. Special-order equipment may be subject to manufacturer restocking or cancellation charges.

• This agreement is governed by the laws of the State of Florida; venue for any dispute shall be Broward County, Florida.

CUSTOMER	PROPERTY	PROPOSAL DATE
Arrigo CDJR Sawgrass	5901 Madison Ave, Tamarac, FL 33321	September 30, 2026

07 / ACCEPTANCE

Authorize your selected option

Select one purchase option. The package price applies only when both systems are accepted together.

☐ **Unit 9 | 15 ton | Second-Floor Executive Area**

$46,096.95

☐ **Unit 10 | 20 ton | Service Advisor Room**

$57,000.00

☐ **Both systems | Combined replacement package**

$96,911.13

O'BRIEN AC & CONSTRUCTION SERVICES, LLC

Tracy O'Brien, President

Signature: _____ Date: _____

ARRIGO CDJR SAWGRASS

Al Garcia, Authorized Signature / Title

Signature: _____ Date: _____

Proposal 2849-AC | Original date: September 30, 2026
Original validity: 30 days from September 30, 2026.