O'Brien AC & CONSTRUCTION SERVICES (954) 205-1381

BMW OF COCONUT CREEK

CUSTOMER	PROPERTY	PROPOSAL DATE
BMW of Coconut Creek	4401 W Sample Rd, Coconut Creek, FL 33073	October 16, 2026

PRIVATE CLIENT PROPOSAL / MORGAN PREFERRED

BMW of Coconut Creek

Commercial HVAC Replacement

TWO LENNOX SYSTEMS / 2 TON + 7.5 TON / COMPLETE INSTALLATION



HVAC REPLACEMENT INVESTMENT

$70,124.00

Lobby Kitchen / 2 ton | Lobby Restrooms / 7.5 ton
Forklift, crane, scissor lift and complete mechanical installation

6% OBRIEN ELITE MEMBER (MORGAN PREFERRED) / $4,476.00 SAVINGS

Property image: BMW of Coconut Creek dealer media

CUSTOMER	PROPERTY	PROPOSAL DATE
BMW of Coconut Creek	4401 W Sample Rd, Coconut Creek, FL 33073	October 16, 2026

01 / MATCHED EQUIPMENT & ELECTRIC HEAT

Your Lennox replacement systems

LOBBY KITCHEN / 2 TON / GROUND-LEVEL CONDENSER

Qty	Replacement equipment	Electrical
1	Lennox ML14KC1-024 condenser 2.0-ton system	208/230V / 1-phase
1	Lennox CBK45UHVT-024 air handler R-454B system	208/230V / 1-phase
1	5 kW electric heat kit Item 27A13	208/230V / 1-phase

LOBBY RESTROOMS / 7.5 TON / ROOFTOP CONDENSER

Qty	Replacement equipment	Electrical
1	Lennox EL090KCSST1G condenser 7.5-ton system	460V / 3-phase
1	Lennox EL090KASD-1G air handler R-454B system	460V / 3-phase
1	10 kW electric heat kit Item 38C15	460V / 3-phase

Both systems include R-454B refrigerant service, compatible controls, electrical reconnection and startup. Refrigerant charging follows manufacturer installation requirements.

CUSTOMER	PROPERTY	PROPOSAL DATE
BMW of Coconut Creek	4401 W Sample Rd, Coconut Creek, FL 33073	October 16, 2026

02 / GROUND-LEVEL & ROOFTOP INSTALLATION

Major work included

LOBBY KITCHEN / 2 TON / GROUND CONDENSER & FORKLIFT

Remove and replace the outdoor condenser at ground level. Provide forklift access and equipment handling to remove and position the indoor air handler. Crane service is not required for this system.

LOBBY RESTROOMS / 7.5 TON / CRANE & LIFTING ACCESS

Provide crane service to remove the rooftop condenser and place the replacement. Use forklift handling, rated material supports and scissor-lift access for removal and installation of the air handler.

ACCESS, DUCTWORK & EQUIPMENT SUPPORT

Protect work areas, provide local equipment access and minor restoration, install necessary duct transitions, seal and insulate connections, and provide suspension hardware and vibration isolation.

REFRIGERANT PIPING, DRAINS & CONTROLS

Prepare or modify accessible refrigerant piping, pressure-test, evacuate, insulate and charge both systems. Complete condensate, overflow protection, electric heat and compatible control connections.

REMOVAL, COMMISSIONING & COMPLETION

Recover existing refrigerant, remove retired equipment and manage disposal. Complete electrical reconnection, startup, operating checks, airflow and drainage checks, final cleanup and handover.

Estimated on-site installation: approximately five working days. Scheduling will be coordinated with your team to limit disruption.

CUSTOMER	PROPERTY	PROPOSAL DATE
BMW of Coconut Creek	4401 W Sample Rd, Coconut Creek, FL 33073	October 16, 2026

03 / OBRIEN ELITE MEMBER PRICING

Your replacement investment

Two complete system replacements delivered as one coordinated project, with member savings applied once to the project price.

SYSTEM REPLACEMENT	BASE PRICE
Lobby Kitchen / 2 ton / ground condenser + forklift	$13,600.00
Lobby Restrooms / 7.5 ton / crane + forklift & scissor lift	$61,000.00
Combined project price	$74,600.00
6% Obrien Elite Member (Morgan Preferred)	-$4,476.00
TOTAL PROJECT INVESTMENT	**$70,124.00**

OBRIEN ELITE CLIENT SAVINGS

$4,476.00

COMPLETE COORDINATED PROJECT

Includes both Lennox equipment packages and electric heat, removal and installation, crane service for the larger condenser, forklift handling for both air handlers, scissor-lift access for the larger system, rigging, connections, local restoration, disposal and commissioning.

MEMBER SAVINGS & TERMS

The 6% Obrien Elite Member (Morgan Preferred) discount is applied once. Pricing is for the coordinated two-system scope. Proposal valid for 30 days from October 16, 2026. Changes outside the listed scope require written authorization.

CUSTOMER	PROPERTY	PROPOSAL DATE
BMW of Coconut Creek	4401 W Sample Rd, Coconut Creek, FL 33073	October 16, 2026

04 / PROJECT TERMS & CUSTOMER ACCEPTANCE

Approval & conditions

PROJECT COORDINATION

We will coordinate equipment delivery, crane setup, forklift and scissor-lift access, protected work areas and installation scheduling with your facility representative.

WORK OUTSIDE THIS PROPOSAL

Major structural reinforcement, primary electrical service or transformer upgrades, sprinkler relocation, hazardous-material remediation, full building-management integration, temporary cooling, major roof replacement and extensive concealed duct or piping reconstruction are excluded.

ADDITIONAL WORK

Work outside the listed scope will be presented in a written change order for customer approval before additional work proceeds. Payment arrangements will be included in the project agreement.

WARRANTY & HANDOVER

One-year O'Brien installation labor warranty from completion. Equipment coverage follows Lennox commercial warranty terms. Startup records and maintenance recommendations will be provided at handover.

CUSTOMER ACCEPTANCE

I authorize the two-system replacement scope at a total project investment of **$70,124.00**, including **$4,476.00 in Obrien Elite Member (Morgan Preferred) savings**.

BMW of Coconut Creek representative / title: _____

Signature: _____ Date: _____

O'Brien AC & Construction Services, LLC

Authorized representative: _____ Date: _____