CUSTOMER	PROPERTY	DATE
Arrigo CDJR Sawgrass	5901 Madison Ave, Tamarac, FL	Oct 12, 2026

PRIVATE CLIENT PROPOSAL / MORGAN AUTOMOTIVE GROUP

Arrigo CDJR Sawgrass

Commercial HVAC Replacement

UNITS 7 + 8 | TWO MATCHING 7.5-TON LENNOX SYSTEMS



TWO-SYSTEM REPLACEMENT INVESTMENT

$132,822.00

Unit 7 | Executive Office Unit 8 | Mezzanine Showroom

02 SYSTEMS • 6% MORGAN PREFERRED DISCOUNT • $8,478 SAVINGS

CUSTOMER	PROPERTY	DATE
Arrigo CDJR Sawgrass	5901 Madison Ave, Tamarac, FL	Oct 12, 2026

01 / MATCHED LENNOX EQUIPMENT

Units 7 + 8 | 7.5 ton each

Lennox commercial split systems | 208/230V / 3-phase | R-454B

Lennox supplier quote #795055 (priced per system; quantity two assumed)

EQUIPMENT / ITEM	QUANTITY
Lennox EL090KCSST1Y outdoor condensing unit	2
Lennox EL090KASD-1Y matching air handler	2
10 kW electric heat kit, 208/230V 3-phase	2

DESIGNATED SERVICE AREAS

- Unit 7 serves the Executive Office. Unit 8 serves the Mezzanine Showroom. Final tag/served zone identification to be checked on site.

REFRIGERANT & EQUIPMENT NOTES

Allow one 20-lb R-454B cylinder per system, with final installed charge based on the Lennox charging procedure, field piping dimensions, line length, and commissioning. Reuse or replace refrigerant lines as required by the verified scope.

REPLACEMENT SCOPE

- Remove and demolish BOTH existing indoor air handlers; supply and position two new matching Lennox air handlers. Disconnect and remove retired outdoor condensers.
- Install all matched equipment and 10 kW heat kits; verify support, access, controls, circuit requirements and compliance before energizing.
- Coordinate lifting access and rigging so both systems can be completed under the same approved work plan. Schedule includes five 8-hour labor days per unit with a planned three-technician crew.

CUSTOMER	PROPERTY	DATE
Arrigo CDJR Sawgrass	5901 Madison Ave, Tamarac, FL	Oct 12, 2026

02 / COMPLETE CONSTRUCTION & INSTALLATION

Major mechanical work

AIR HANDLER & DUCT DEMOLITION

Demolish both existing air handlers, disconnect existing services safely, dismantle affected duct sections, remove demolition debris, and install required replacement transitions.

DUCT FABRICATION & SUSPENSION

Fabricate and install necessary duct transitions and modifications, seal exposed joints, and provide new suspension hardware, springs, nuts and bolts as required.

WALL CUT-THROUGH & ACCESS

Perform planned wall cut-through and access opening; protect adjacent finishes, sleeve and seal pipe routes, and coordinate access equipment including lull, jacks and required lifting.

REFRIGERANT LINES & COMMISSIONING

Modify condenser piping, replace or flush serviceable line sections as specified, pressure-test, evacuate, insulate, charge with R-454B, and perform full start-up checks.

ELECTRICAL WORK

Complete necessary equipment electrical work for the new 208/230V 3-phase systems and 10 kW heaters, verify disconnects, wiring, overcurrent protection, grounding and electrical safety.

DEBRIS & WASTE

Provide dumpster and disposal logistics for HVAC and duct demolition waste, with lifting/rigging coordination and housekeeping.

CUSTOMER	PROPERTY	DATE
Arrigo CDJR Sawgrass	5901 Madison Ave, Tamarac, FL	Oct 12, 2026

03 / INDIVIDUAL & COMBINED PRICING

Your replacement investment

The same full system scope is available for each area. The 6% Morgan Preferred Discount applies when both Units 7 and 8 are authorized together.

INDIVIDUAL REPLACEMENT	PRICE
Unit 7 | Executive Office | 7.5 ton	$70,650.00
Unit 8 | Mezzanine Showroom | 7.5 ton	$70,650.00

TWO-SYSTEM PACKAGE	AMOUNT
Combined individual replacement prices	$141,300.00
6% Morgan Preferred Discount	-$8,478.00
TOTAL BUNDLE PRICE	**$132,822.00**

TOTAL CUSTOMER SAVINGS

$8,478.00

COMBINED APPROVAL INCENTIVE

The 6% Morgan Preferred Discount requires approval of BOTH Units 7 and 8 together. Each unit may be approved separately at its individual price. Additional scope requires written authorization.

CUSTOMER	PROPERTY	DATE
Arrigo CDJR Sawgrass	5901 Madison Ave, Tamarac, FL	Oct 12, 2026

04 / EXCLUSIONS, COORDINATION & ACCEPTANCE

Approval & conditions

WORK BY OTHERS — NOT INCLUDED IN OUR PRICE

- Sprinkler disconnect and relocation will be completed by others, including required fire-protection authorization, testing and reinstatement.
- Window removal and restoration, if required for equipment access, will be performed by others. Coordinate before demolition or delivery.

OTHER TERMS

- Assumes site-approved access, safe structural supports and suitable electrical service. Major structural reconstruction, primary service/panel upgrades, and unforeseen concealed conditions are excluded unless separately approved.
- Permits/inspection fees are excluded unless explicitly agreed. Pricing is subject to site verification and supplier availability; valid for 30 days from October 12, 2026.
- One-year O'Brien installation labor warranty from substantial completion; equipment warranty follows Lennox manufacturer terms.

SELECT PURCHASE OPTION

[ ] Unit 7 only — Executive Office	**$70,650.00**
[ ] Unit 8 only — Mezzanine Showroom	**$70,650.00**
[ ] Both — 6% Morgan Preferred Discount	**$132,822.00**

O'BRIEN AC & CONSTRUCTION SERVICES, LLC

Tracy O'Brien, President

Signature: _____ Date: _____

ARRIGO CDJR SAWGRASS

Al Garcia, Authorized Representative

Signature: _____ Date: _____